BRUHATH BANGALORE MAHANAGARA PALIKE

Rajarajeshwari Nagara Division

SCHEDULE-B

Name of Work :Improvements to drain at 2nd main of Muthyalanagar in ward no 17.

Agency				Sri G VASU	
Sl No	Qty	Item Description	Unit	Rate	
				In Figures	In Words
1	2	3	4	5	6
1	478.80	Removing B.S.Slab of drain & stacking as per specification	sqm	53.00	Rupees Fifty Three Only
2	171.00	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manualluy (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled and after breaking of clods and neatly dressed as per specification	cum	132.00	Rupees One Hundred Thirty Two Only
3	45.60	Earth work excavation for foundation of building water supply sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width in hardsoil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications.	cum	239.00	Rupees Two Hundred Thirty Nine Only
4	478.80	Refixing stone slabs of drains and pointing in C.M (1:3) as per specifications.	sqm	74.00	Rupees Seventy Four Only
5	216.60	Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum	114.00	Rupees One Hundred Fourteen Only
6	30.40	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregate @0.85 cum and fine aggregate @0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4501.00	Rupees Four Thousand Five Hundred One Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP

Sl No	Qty	Item Description	Unit	Rate	
				In Figures	In Words
1	2	3	4	5	6
7	608.00	Providing and constructing preacast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry(quoin, jamb, closer blocks) with solid c oncrete blocks of size 40x20x20 cms confirming to IS:2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	sqm	970.00	Rupees Nine Hundred Seventy Only
8	38.00	Providing and laying in position plain cement concrete of mix M15 with cement @240kgs with 20mm and down size graded granite metal, coarse aggregate @0.878cum and fine aggregate @0..459 cummachine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5013.00	Rupees Five Thousand Thirteen Only
9	205.20	Providing 10 cm thick granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.	sqm	607.00	Rupees Six Hundred Seven Only
10	684.00	Providing one line dressing to granite stone slabs / granitestone masonary as per specifications	sqm	460.00	Rupees Four Hundred Sixty Only
11	1689.00	Providing and fixing Pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with toop and bottom wideth 114 and 165 mm respectively 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, includng form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unoading lead and lift transportatin etc, complete.	nos	280.00	Rupees Two Hundred Eighty Only
12	342.00	Providing and applying ready mix priming coat over concrete/ masonry/asbestos cement sheet/ plastered surfaces including preparing the surface after thoroughly cleaning of oil grease, dirt and other foreign matter, and sand preparing including cost of materials, labour complete as per specifications.	sqm	25.00	Rupees Twenty Five Only
13	342.00	Providing and applying floor painting with ready mix paint in two coats (excluding primer coat) on new concrete/asbestos cement sheet/plastered surfaces brushing to give an even shade after preparing the surface after througly cleaning oil dirt, dust other foreign matter and sand papering including cost of all materials, labour complete as per specifications.	sqm	48.00	Rupees Forty Eight Only
14	3798.00	Providing chamfering edges to stone slabs 2.5 cms, wide as per specifications (only chamfered length shall be recorded)	rmt	30.00	Rupees Thirty Only
15	40.00	Providing and fixing M.S.Gratings as per direction of Engineer in charge of work	each	94.00	Rupees Ninety Four Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP